



Shelby County Landfill Turn Lanes and Access Road

ADDENDUM NO. 3

Date: November 8, 2023

RE: Shelby County Landfill Turn Lanes and Access Road

BID DATE AND TIME:
November 9, 2023 at 2:00 p.m.

Location for the bid opening remains the Shelby County Manager's Office, located at 200 West College Street, Room 123, Columbiana, Alabama, 35051

Questions and Clarifications:

Q1. – Where is the 46 LF of Type N curb located?

A1. – The 46 LIN FT is for item 623B-001 Concrete Curb, Type N, Special. It is for the concrete safety noses and it is measured around the perimeter of the noses. There is no Type N curb since this is a monolithic concrete island.

Q2. – If we hit bedrock in the excavation will this be considered part of the unclassified excavation or handled as a separate item?

A2. – All required excavation is covered under the item 210A-000 Unclassified Excavation pay item. It is the responsibility of the contractor to investigate field conditions onsite to determine what is required to perform all excavation.

Q3. – The plans call for a junction box to be installed at Hwy 70 Station 12+22.01 to extend the existing cross drain, if shoring is required to maintain the existing shoulder and safe conditions for traffic will this additional work be addressed by change order or will it be the contractors responsibility for this work?

A3. – Any shoring or temporary support required to protect the existing roadway embankment and maintain the existing travelway of Hwy 70 as well as any protective measures to ensure safe working conditions during this work shall be subsidiary to pay item 621A-009. Any determined work scope that is not specifically addressed in the project plans shall be submitted by the contractor for approval prior to work being performed and upon approval shall become part of the contract project plans.